BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Project Division

Work Slip: As per Std Tender Documents

Name of Work: Improvements and Development and widening of road from National Highway to Railway Line via Nitte Meenakshi College Road till BBMP Limits

Estimate Amount:- 15,00,00,000.00

Name of Contractor:- M/s SLP Infra Engineers Pvt Ltd[Sri H.S Yashwanth Gowda]

Approved amount:- 12,57,09,094.00

Tender premium:- 1.00%

Sl. No.	Description of Work	Unit	Qty as per ScheduleB			Total Qty Executed	Qty. as per Actuals upto 125%			Qty. as per Actuals above 125%			Total		Difference		Remarks
			Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount	Qty	Amount	Excess	Savings	
1	2	3	7	8	9	10	11	12	13	14	15	16	10	17	18	19	20
10	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	72.00	5472.77	394039.44	369.14	90.00	5472.77	492550.00	279.14	5472.77	1527661.00	369.14	2020211.00	1626171.56	0.00	
															1626171.56		

Note: Percentage of Workslip over the sanctioned Estimate=Excess amount over the approved amount/ Approved Amount x 100

Approved Amount =	125709094.00
Excess Amount =	1626171.56

$$\text{Percentage of Worslip} = \frac{\text{Excess Amount}}{\text{Approved Amount}} \times 100$$

Percentage of Worslip =	1.29	%

SLP INFRA ENGINEERS PVT. LTD. BANGALORE

Assistant Engineer

Assistant Executive Engineer

Executive Engineer

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ